



WindFloat Pacific OSW Project

BOEM Workshop Sacramento, CA July 29, 2014

The WindFloat

Turbine Agnostic

- Conventional: 3-blade, upwind
- Partnership with manufacturers
- No major redesign
 - Control system software
 - Tower structural interface

Static Water Ballast – Stability

Used to achieve operating draft

Heave Plates – Dynamic Stability

- Move platform natural response above the wave excitation (entrained water)
- Viscous damping reduces platform motions

Hull Trim System – Efficiency

- Tower is vertical No mean pitch
- Closed-loop with redundant path



Turbine Lighting

Turbine Nacelle

- Turbine Blades

Gangways

- Mooring System and Anchors

Heave Plates and Stiffeners

WindFloat 1: Successfully Operating for Over 2.5 Years



- Installed off of Northern Portugal in October 2011; still producing today
- Generated and delivered over 10 GWh of energy to Portuguese Grid
- Technical availability over 93%
- Performed through extreme weather events, including waves over 15m
- Energy output consistent with onshore turbine under same wind conditions







WF 1 - Anchors








WindFloat 1 - Performance Demonstration





WindFloat 1 - Performance Demonstration

During 2012 and 2013 extreme weather conditions were faced

Sig wave height: 9,05 m

- Max wave height ≈16 m
- No structural damages


renewable energy delivered

Wave Height [m]

WindFloat 1 - was designed to operate up to 6.6 m significant wave height

• This limit was exceeded only 1% of the time during the year resulting in low unavailability due to weather conditions

Extreme events







NOVEMBER 3RD,


STORM #1²⁰¹¹ Hs > 8m Hmax > 15m

WindFloat Pacific – Global Sizing Scale-up 2MW to 6MW

Dimensions	2MW Prototype	6MW					
Rotor Diameter	80m	154m					
Draft	13.7m	18m					
Tower height	56m	88m					
Column height	23.2m	27.5m					
Column diameter	8.2m	10.5m					
Column to column	38m	50m					
WEP Length	12m	13.2m					
Displacement	2800tonnes	6000tonnes					



WFP: Unlocking the West Coast Offshore Wind Potentia







Infrastructure and Supply Chain

- Validate and identification future West Coast infrastructure to support US offshore wind energy development
- In depth study and analysis of serial production benefits of the WindFloat technology

Deepwater Offshore Wind Resource Assessment

- Development and validation of a method suitable for deepwater locations
- Design basis development and energy generation predictions

Deployment of state of the art 6MW+ wind turbines offshore

Offshore Installation and O&M

- Multiple offshore wind turbines and transmission infrastructure without ANY offshore lifting or piling activities
- Design and analysis of offshore O&M methods and procedures for floating wind

First step in establishing an industry





Larger capacity, 6MW+ Turbine

• Direct drive turbines increase energy capture and improve reliability

Floating Support Structure

- Stable, cost effective floating platform
- Structurally decoupled from bottom conditions
- Float out installation process utilizes inexpensive, widely available, Jones Actcompliant vessels
- Tow-to-shore option for major repairs reduced O&M costs and increases uptime
- Quayside installation and commissioning of turbines to reduce commercial and schedule risks

25-year design life increases lifetime generation and reduces financing costs Simple decommissioning process reduces costs and improves safety




WFP: Key Location Features















Strong wind resource

• Annual NCF ~ 42.5%

Deep water offshore

- Generally sandy/silty bottom
- Avoidable rocky outcroppings

Industrial community

- Deep, protected harbor
- No Air-draft issues

Organized Fishing Presence

Consensus on project location

Existing BOEM state task force (OR) Favorable state policy disposition


- Renewables/ocean energy
- Market pull from Regional Utilities

124.7	-124.6	-124.5	-124.4	-124.3 -12
8.55 8.54	8.53 8.51	8.49 8.44 8.	.38 8.3 8.19	8.04
8.57 8.57	8.56 8.54	8.51 8.46 8.	.38 8.3 8.17	8.01
8,6 8,59	888 8.56	8.53 8.47 8.	.39 8.3 8.15	7.94
3.63 8.62	8.61 8.6	8.56 8.49 8	.4 8.28 8.1	7.8
8.65 .66 8.65	8.65 8.63	8.59 8.52 8	.4 8.26 8.02	/
3.69 8.69	8.69 8.67	8.63 8.55 8.	42 8.26 7.92	Legend Project Locati
Pr 1.73 8.73	eject Location 8.73 8.71	8.67 8.59 8.	43 8.24 7.75	\checkmark
8.77 8.77	8.77 8.76	8.71 8.63		Coos Depth Contou
3.81 8.82	8.82 8.81	8.76 <mark>8.66</mark> 8.	46	Bay Mean 90-m ₩
3.85 8.86	8.87 8.86	8.8 8.69 8.	.47	8.01
8.9 8.91	8.91 8.9	8.84 8.71 8.	47	8.43
<u>1.94</u> 8.95	8.95 8.94	8.86 8.73 8.	.46	8.64
Conic 9	8.99 8.96	8.88 8.73 8.	44	0 1
-124.7	-124.6	-124.5	-124.4	-124.3 -12




Proposed Project Site

- Lease application filed with BOEM May 14th 2013
- Application area for OCS lease blocks (and aliquots) to BOEM
- ~18 miles offshore
- Project will be in about 350+ meters (~1200 feet) of water
- Generally sandy/silty bottom









Preliminary WFP Mooring Configuration

WFP: Visual Effects: Turbines off coast of Coos Bay





View from cable landing

Zoomed approximately 4 times

Views from other shore locations will be very similar (for example Gregory Point)





Concern	Modification
Interference with commercial fishing activities	Project site moved from ~10 miles offshore to approximately 18 miles offshore to reach 200 fathom depth.
Threats to migratory seabirds	Turbine blades will rotate at a minimum of 30 m above sea surface; no further changes needed.
Presence of Wind Floats potentially threaten marine mammals, sea turtles, and fish	Gather all available data on presence of marine animals. Determined that most migratory species are not present in large numbers; no changes needed.
Concerns about viewshed from culturally sensitive lands off Gregory Point	Additional visual effect studies will be conducted to demonstrate how small turbines will look 18 miles offshore.
Concerns about habitat destruction of rocky reefs on the WFP site and along cable route	Bathymetric surveys and sub-bottom profiling surveys used to identify sensitive areas; cable route modified to traverse around identified rocky reef.





50% FEED

• ABS Approval in Principle in hand

Site Identification

• Endorsement from Local Fishing Fleets

Initiate Permitting Process

- DNCI from BOEM establishes site control
- Aggressive Approval Schedule: Permits in Hand Q2 2016

Public Approval

• Explicit Committed Support from NW Governors and stakeholders

Project Finance and Future Cost-share

• Deepwater Wind's experience structuring off-takes and raising capital





Engineering & Design

- 100% FEED
- Fabrication strategy identified and vendor quotes received

Installation, O&M

• Installation procedures and O&M methodology documented

NEPA & Permitting

- Material progress on major regulatory processes
 - Submission of Construction and Operations Plan (COP)
 - Lease issuance (target Q2 2015)

Off-take & Grid Interconnection

- Material progress on off-take agreements
- Material progress on interconnection studies/agreement



- Acquisition of all permits
- **Execution of contracts**
- **Ordering of steel and components (i.e. turbines)**
- Fabrication, Delivery, Assembly
- Installation
- Commissioning

- Expected Commissioning before end 2017 -

Post – installation monitoring campaign



WFP: Turbine Installation at Quay Side




Quay Side Installation

- In Coos Bay
- No special vessel
- Floating platform
- (Ballast water to keep platform even-keeled while transiting from 6 to 12m draft)
- Shore requirements:
 - Water depth > 12m
 - No dredging / civil works
 - Crane at quay (may be rented)

Time Frame: 2 days / platform

Weather independent in summer



WFP – Schedule: Aggressive but Achievable

Activity Name	Start Date	Finish Date	2013				2014			2015				2016				2017			
Proving Hume			Q 3	Q 4	Q 1	Q 2	Q 3	Q 4	Q 1	Q 2	Q 3	Q 4	Q 1	Q 2	Q 3	Q 4	Q 1	Q 2	Q 3	Q 4	
VindFloat Pacific	10/1/13	10/1/13		Ý																	
50% FEED	1/1/13	2/17/14			I																
Downselect	2/18/14	5/12/14			_	<u> </u>															
100 % FEED	5/13/14	2/16/15							-												
Turbine engineering (turbine vendor)	5/13/14	2/16/15																			
Cable engineering (3rd party)	5/13/14	2/16/15					-														
Hull & mooring engineering	5/13/14	2/16/15			1	-		-	_	-	1		1		S 5	-	1 S		1 S	-	
3rd party certification	5/13/14	2/16/15			9 <u>0</u>	1 *		-			9 <u>0</u>				14 O		12 J		12 D		
Procurement/Detail Design	6/10/14	7/1/15			S						-		1		N		1		S		
RFQ preparation	6/10/14	8/4/14	12		12/	🛀					12 9				82 D		17 <u></u>		12 9		
Vendor quotes	6/10/14	9/29/14			1 5	1		-	1 I I I	3	1		1		N	-	- E		10 S	-	
Vendor selection	9/30/14	12/22/14						*							<u>ba</u>		P		<u>-</u>	-	
Detail design	2/17/15	7/1/15			1		1	-	\ 📥		-		1	-	1		1		1	-	
Permitting	3/27/13	2/3/16							1			1		-	la0		0	-	<u>12</u> 0	-	
OCS Lease Application	3/27/13	5/19/15									2		1		N		1 6		N	-	
Site Characterization/Env Studies	3/27/13	10/21/14									9 <u> </u>				2 <u> </u>		12 D		12 S		
COP	3/27/13	3/27/13			1						2 5		1		N		1 1		1		
NEPA Document	5/2/13	2/3/16	-		6				1						e		92	-	S		
Interconnection studies	12/11/14	5/17/16			1			_		N					N		1 1		1		
Project Financing	5/13/14	6/19/15		-		<u> </u>									<u>ia</u>		· · · · ·		<u> </u>		
JV Formation	5/13/14	7/31/14				+ +						-			1		1		1		
PPA Negotions	8/4/14	3/31/15			<u>k</u>						<u> </u>				<u>.</u>		· · · · · ·				
EPC Negotiations	8/1/14	3/2/15				8 - 2	•				3				3		3		3		
Funding arrangements	9/29/14	6/19/15	<u>.</u>		12 D						9				12 (92 - O	-	12 j		
FID	7/1/15	7/1/15			1				1		t				1		1 1		1		
Execution	7/2/15	12/8/17			92				14		Ľ	-		-			-				
Fabrication	7/2/15	4/28/17			1		1		1		r	-									
Order steel	7/2/15	10/21/15		-							ŧ				ez		92	~	2 S		
Fabrication drawings	7/2/15	10/21/15			1		1				÷				1 1				N 5		
Hull fabrication	2/4/16	4/28/17					· · · ·							4			с – э	-	k		
Installation	5/1/17	10/13/17																		-	
Export cable	8/3/17	8/3/17													la 0			ľ		-	
	5/1/17	7/21/17		-		-		-				-		-				+			
Mooring pre-lay	7/24/17	10/13/17															-	_	+		
Inter-array cable	7/24/17	10/13/17									-								÷		
Towing and hook-up																			-	ł	
Commissioning	10/16/17	12/8/17												1	3					_	
			Third Q	Fourth Q	First Q	Second Q	Third Q	Fourth Q	First Q	Second Q	Third Q	Fourth Q	First Q	Second Q	Third Q	Fourth Q	First Q	Second Q	Third Q	Fourt	









Oregon Governor John Kitzhaber

"We are committed to working with Principle Power to responsibly site this project, and ensure that they can move through the state permitting process in a timely and efficient manner. We commend Principle Power for their effort to engage a diverse group of stakeholders, particularly the fishing community, in identifying their proposed site. We also support the arrangement of power purchase agreements with parties in our state, overcoming one of the key challenges for new energy technology development."



Washington Governor Jay Inslee

"While costs of energy from demonstration scale projects are typically above market, our state requirements and incentives encourage development and investment in these types of projects, while successfully creating new jobs. I am committed to further enhancing conditions within our region to support the wide scale use of clean energy resources...I urge you to continue supporting WindFloat Pacific."





Retirements of fossil and nuclear power plants


- Creates near-term need for large-scale resources
 - San Onofre, CA 2150 MW
 - Boardman, OR 550 MW
 - Centralia, WA 1340 MW

West Coast has excellent offshore wind resource

- Can deliver energy directly into denselypopulated coastal areas
- Winter peaking supply corresponds to peak demand periods

Like BIWF, WFP is critical to the West Coast to

- Build capabilities
- Demonstrate feasibility
- Position to add large-scale offshore wind resource on line







"This is a really exciting and innovative project. It involves a floating technology that has enormous potential on the West Coast, where the shelf drops off steeply, as well as around the world."

BOEM Director Tommy Beaudreau, DNCI Announcement Press Event, Portland OR, February 6, 2014.

"I will say with regard to timing that we certainly feel a sense of urgency. We'll be working in concert to expedite this to the extent that we can." Secretary of Interior Sally Jewell, DNCI Announcement Press Event, Portland OR, February 6, 2014.













