Table 3.3.5-2

Interconnect Cable System Distance From The Monomoy Shoals Alternative Site To The Barnstable Substation

115 kV Cable Length	Total Distance
Electric Service Platform to Barnstable Substation	29.8 miles
Upland cable	5.9 miles
Submarine cable	23.9 miles
Submarine cable Outside of 3-mile limit	2.9 miles
Submarine cable Inside of 3-mile limit	21.0 miles

Table 3.3.6-1

Examples of WTG Grid Spacing for Offshore Wind Parks

Wind Park/Location	Spacing (rotor diameter)			Ratio
Horns Rev/Denmark	7.0	x	7.0	1.0
Nysted/Denmark	10.4	x	5.8	1.8
Kentish Flats/Denmark	7.8	x	7.8	1.0
Barrow/United Kingdom	8.3	x	5.6	1.5
Burbo/United Kingdom	6.7	x	5.0	1.4
North Hoyle/United Kingdom	10.0	x	4.4	2.3
Average	**8.4**	**x**	**5.9**	**1.5**
Cape Wind	**9.0**	**x**	**5.7**	**1.6**